

"GREEN SUBSIDY"

TO MODERNIZE THE BOILER STATION IN THE QUARTER IN KARAGANDY

Series of publications on energy service initiatives, supported by UNDP-GEF within the Project "Sustainable cities for low-carbon development"

Brief description of the Project:

Boiler in the microdistrict in Karaganda, year of commissioning – 1960;
Provides heat supply for 5 buildings/constructions of area 26 935 sq. m.;
Equipment depreciation by begin of 2017 – 90%;
Actually generated capacity – 21 672 Gkcal/season;
Annual current extra costs to maintain the facility's operation – 45,6 mln tenge

AFTER MODERNIZATION



BEFORE MODERNIZATION



Analysis of current situation

№	Title	Current condition	In case of modernization	Effect from modernization
1.0 Technical parameters				
1.1	Capacity of the boiler station	10 MW (operational) 10 MW (reserved) 10 MW (non-operational)	2,5 MW (operational) 2,5 MW (operational) 2,5 MW (reserved)	Reduction of capacity by 62,5%
1.2	Length of heating nets	980 m	700 m	Reduction of energy losses by 28,5%
1.3	Energy consumption, coal	7 287 t.	4 410 t.	Saving of 39,5%
1.4	Energy consumption, electricity	908 250 kW	756 000 kW	Saving of 17%
1.5	Energy consumption, water	5 492 m ³	1 470 m ³	Saving of 83,2%
1.6	Coefficient of efficiency	28%	70%	Increase in 2,5 times
2.0 Economic parameters:				
2.1	Energy resources consumption	29 000	19 500	Reduction of costs by 32,5%
2.2	Costs for repair and maintenance servicing	20 000	600	Reduction of costs by 97%
2.3	Removal of burnout and slags, other payments	800	2 100	Increase of costs by 262%
3.0 Parameters of people's comfortable stay				
3.1	Average seasonal temperature in the premises\rooms	16 °C	19 °C	Increase of temperature by 19%
4.0	GHG emissions, tons of CO₂	7 510,5	4 506	3 004,2



Cost of investment into modernization of quarter's boiler

№	Title	UoM	Amount of the investment	Incl. the credit in STB
1	Purchase of boiler equipment	thou. Tenge	145 000	130 000
2	Total:	thou. Tenge	145 000	130 000

Financial support with loan banking – 130 000 thous. Tenge

№	Title	Ед. изм.	1-season	2-season	3-season	4-season	5-season	6-season
1.0	Saving with modernization	thous. Tenge	27 600	29 532	31 599	33 811	36 178	38 710
2.0	Loan disbursement to the Bank	thous. Tenge	37 396	34 557	31 719	28 881	26 042	23 204
2.1	Incl. % rates by loan	thous. Tenge	15 729	12 891	10 052	7 214	4 376	1 537
3.0	Economic opportunity (p.1.0 – p. 2.0)	thous. Tenge	-9 796	-5 025	-120	4 930	10 136	15 506
4.0	Subsidy by DAMU-UNDP-GEF	thous. Tenge	12 007	9 840	7 674	-	-	-
5.0	Economic opportunity with support of DAMU-UNDP-GEF (p.3.0 + p.4.0)	thous. Tenge	2 211	4 815	7 554	4 930	10 136	15 506

SCHEME OF PROJECT IMPLEMENTATION ON MODERNIZATION OF BOILER STATION IN THE MICRODISTRICT



SUMMARY:

- Implementation of the Project allowed the Owner of the boiler station to:**
 - Save energy/financial resources by **27 600 thous. Tenge/season**;
 - Reduce CO₂ emissions into city atmosphere by **3 004,2 tons/season**;
 - Improve the conditions of comfortable stay of **660** employees in the premises\rooms and **1,6 mln.** visitors/year;
 - Minimize the accident situations at boiler stations
- Support of DAMU-UNDP-GEF provided:**
 - The opportunity to implement the Project;
 - The opportunity to settle with the Bank due to saving received without additional costs
- Subsidy efficiency:**
 - 1 Tenge of subsidy has attracted 8 Tenge of resources from all financing sources;
 - 1 Tenge of subsidy has reduced **0,14 kg of CO₂** or **2,7 kg CO₂** over the life cycle of the boiler station